



**Notes:**

1. Concrete 35 Mpa min. Air 5-7%
2. Approx. weight 3600 kg.
3. Unit can be set in place by Acton Precast truck if site is ready at time of delivery.
4. Maximum Load: 5000 kgs.

**LPC80G**

3 Ph Transformer Base - Guelph

Acton Precast Concrete Limited